A Journey of Revitalizing **Forest Meadow Junior High School Through Innovative Construction and Overcoming Unexpected** Challenges

Wednesday, May 8, 2024





GARY AANENSON, CORE CONSTRUCTION LE KORTE, RICHARDSON ISD

Presenters



LE KORTE, AIA | NCARB | LEED BD+C Executive Director of Facilities Planning, Design and Construction Richardson Independent School District



GARY AANENSONExecutive Vice President

CORE Construction



55 Campuses

38,000 Students

4 Learning Communities









Middle School Learning Transition



Mitigate space concerns at elementary schools

Provide sixth graders access to wider and advanced academic offerings, extracurricular opportunities in fine arts, athletics, and other areas of interest

DESIGNER

Perkins + Will

CONTRACTOR

CORE Construction

\$50M

58,305 SF

Addition & Reconfiguration



23 Classrooms



Weight/Locker Rooms



Storm Shelter



New Tennis Courts



Science Lab Renovation




Final Exterior



Parking & Site Work



Cafeteria Expansion & Kitchen Reconfiguration







Client Challenges

2


Design Challenges

3

Contractor Challenges

CLIENT CHALLENGES 1967
What did the world look like in the 1960's?





What will the world look like in 2070?

How do we take a building from the 1960's and make it flexible enough to adapt to what will come in 2070?



Challenges of Community Engagement During COVID

Virtual Program Planning Committee (PPC) Meetings

- How to handle building adjacencies virtually?
- How to do planning workshops virtually?

Establish a Middle School

Keeping the Community Informed Throughout the Process

 How could we as a District help keep the community thinking forward during such a time of uncertainty?



Budget Challenges

Established Bond 2021 Budgets Around 2019 - 2020

Drawings went out to bid in January 2022

Original Budget of Forest Meadow \$30M

Guaranteed Maximum Price \$50M

No windows or access to outside spaces easily!

More windows and natural light.

What is not successful about your building?

interior facelift needed

Difference in feel of F Hall vs. original sides. Wanting new access to technology, new interiors, updated feel.

More natural light please!

Outdated

Not a lot of central locations for students to work in groups.

interior facelift needed

What is successful about your building?

Easy to navigate around the building.

I love the central location of the library! It is easily accessible on both sides of A and C halls.

Students and staff are awesome!!


The large gym is great.

I love the openness of the cafeteria. It is a friendly feel that you can access from all over the building!


As a coach, We like the Green space and access to the athletic fields.

No hiding places.

Existing Site Plan



Proposed Site Plan






Market in the Meadow


















Existing Floor Plan – Level 00 WEIGHT ROOM ATH LR GYM FINE ARTS





CONTRACTOR CHALLENGES


Phasing Plans



Phase 1A - Interior Mobilization/Renovation June 2022 – August 2022 (DAH) € CIIID Temporary 15'-0" Wide Hallway Full-Height Construction Temporary Admin & Counseling 4,686 sf (m) New Pop-Up Construction Area C: Conference Rm/ Testing & Materials Students in Portable for life of Area B: (2) Private Offices (1) Executive Office Students in Portable for life of Entrance & Reception New Temp Wall


Phase 1 – Site Work

July 2022 – November 2022 *Contingency Upon Building Permit



Phase 2 – 2-Story Classroom Wing & Athletics July 2022 – December 2023 *Contingency Upon Building Permit EAD (A0) (B.0) ERITHGUARDE PLC ERRC HOME BY CITE nights/week CHI. T.T.T.T A CONSTANT GARGINA. (E4) (E5) FLOOR PLAN LEGEND LEG ... ENTING SOPICE CONSTANT CONSTRUCTION FLOOR PLAN NOTES BY NUMBER <<p><<< Indicates Sheet Keynote on Plan</p> SH SJ SK SL SA SB SC


Phase 2 - Site Work - Thanksgiving & Christmas Renovation November 2022 - January 2023




Phase 2A - Site Work View June 2023 – August 2023 2001 WHING BOLLEVARD KISS 8 Portable Classrooms Fence Around REMOVED SITE PLAN Portables SUMMER THE VILLA CREEK DALL **NOTES BY NUMBER** 2023) RICHARDSON NOEPEND <<c Indicates Sheet Keynote on Plan Joseph Rodates Sheet Keyndes on Plant [Institute ELECTION Service State of the Col. [Institute SELECTION Service State of the Col. [Institute SELECTION Service State of the Col. [Institute SELECTION SERVICE SELECTION SERVICE SERVI FOREST MEADOW MIDD Area of Paving to be Completed by NOV 2022 **LEGEND** Area of Paving to be Completed by Aug 2023 RISD, PW & **CORE Parking** Subcontractor **Parking CORE Trailer Material Laydown** & Subcontractor EXISTING EDUCATION BUILDING FF LEVEL 0 = 583.45° FF LEVEL 1 = 593.5° DOUBLE STORY **Parking Connex Boxes** (170) Construction \mathbf{M} EXISTING EDUCATION BUILDING F.F. = 578.5° SINGLE STORY WIMEZZANINE Entrance/Exit Bus Drop Off Parent Drop Off Site Fence WHITEHURST DRIVE SITEP Area of Paving to be Completed by Aug SHEET NUI 2022 A01-0

Phase 2A - Remaining Interior Renovation & Roofing June 2023 – August 2023 EAE COMMON LINES (A0) (B.0) CINE I KITCHEN TO BE COMPLETED **OVER SUMMER** Pre Abatement Demo - 5/30-6/5 and Build Back **CORE Build Back** 6/8/23 - Aug 2023 6/16 - September 2023 FLOOR PLAN LEG COLUMN CONSTANT **OMPLETION DEC 202** FLOOR PLAN **NOTES BY NUME** CARREDO occ Indicates Sheet Keynote on **Temporary Student** Entrance & SJ SK SL


Phase 2A – Site Work View August 2023 – January 2024






Phase 2B - Remaining Interior Renovation - Level 01 August 2023 - January 2023 (EAE) EAD (A.0) (B.0) HOME EC ENT CTR) (F) **包. E. B. E. E. E.** 田 REFER TO ASSISTNESS FOR HISCOLL CWETERA (E3) (E4) (E5) (E6) (E7 (E8) FLOOR PLAN LE PEATEUP GUEROON GUEROON LEUR **MILESTONES TO TURN** OVER AREA A & B: DECHLISP FLOOR DRAIN -AIR ON 9/25 & 10/1 -AREA B FEMA INSPECTION EMPRO SCENCE -AREA B CURTAIN WALL INSATLLATION CONSTANT -PERMANENT DRY IN; AREA A EAST CONSTRUCTION **CURTAIN WALL** -LEARNING STAIR HILL COMPLETION DEC 2023 FLOOR PLAN HANDRAIL INSTALLATION NOTES BY NUM CHARRESON CASSICON WINTER BREAK: - TRANSFORM RECEPTION TO EXISTING CLASSROOM & CLOSE IN VESTIBULE occ Indicates Sheet Keynote or Temporary Student Reception SH SA SB SC SJ SK SL

Phase 2A – Site Work View January 2024 – May 2024



Phase 2B - Remaining Interior Renovation - Level 01 January 2024 - May 2024 EAE (EAD) (A0) (B.0) PROVIDE MINIAUM Y- IF O OF EVERY DOOR WITH A CLEAR AT THE PULL SIDE SPECIFICALLY DIMENSION HOW AC DISCUS CTE PERCENNICA T.T.T.T.T PEFER TO ASS SERIES F CAPETIDIA WINTER BREAK LIBRARY SCOPE OF A (E3) (E4) (E5) (E2) (E7 (E8) WORK: FLOOR PLA Move out furniture - Demo ceilings - Build out corridor Cut in new storefront SPRING '24 NIGHTS/WEEKEND WORK: DATES NOOMED - Ceiling installation -Lighting installation - T&B, Paint (Striping), Wall Tile - Green room door (368) (At)-DISTRIBUTE OF THE PARTY OF THE (S2.2) S2.8 S3 SOENCE (1938) FLOOR **NOTES BY** CLASSICAL LANG. S2.4) (84) SD SE SF SH SJ SK SL SA SB SC





PRINCIPAL SUSAN BURT

2022-2023 Principal of the Year!





FooThishis...




CONTRACTOR CHALLENGES


Unique Features



Waterproofed Temporary Wall



Storm Shelter Tie-in to Existing Building



Abatement of an Occupied Campus



Elevator Installation to Existing Building

